

Base Line through T. 1 N., R. 32 E.

Chains	Thence West on true line on S. boundary of sec. 35. Var. 20° East.
.20	Old bed of Mc Kay creek, course N.
4.00	Leave thick brush.
11.50	McKay creek, 50 lks. wide runs N. W.
20.00	Leave creek bottom and ascend.
28.00	Intersect Umatilla Reservation boundary, and set a post 4 ft. long, 4 ins. square, 24 ins. in the ground for closing cor. to Umatilla Reservation marked U. R. C. C. on E. face and S. 35 on N. face. Dug pits, 18 x 18 x 12 ins., N. and S. of corner, 5½ ft. dist. and raised mound of earth ½ ft. high, 3½ base around post.
40.00	Set basalt stone, 10 x 9 x 8 ins., 6 ins. in the ground for ¼ sec. cor., marked ¼ S.C. on N. face, dug pits, 18 x 18 x 12 ins., E. and W. of stone, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it.
54.00	Summit of ridge.
80.00	Cor. to secs. 34 and 35, T. 1 N., R. 32 E. and place of beginning.
	Land, gently rolling.
	Soil, 1st rate.

+200

General Description

These two miles of line pass across McKay creek and rolling hills on each side. Soil generally an ashy loam with some rock on Eastern side of creek. Very little grass. Creek bottom is 20 chs. wide and its soil is rocky: with some balm, alder, thorn, summach & timber and brush. Surveyed June 8, 1887.

Exterior Lines of T. 1 N., R. 32 E.
Surveyed by Currin and Noland, under special contract.
Dated May 4, 1887.

Beginning on the Base Line at the cor. to Tps. 1 N., Rgs.
32 and 33 E.

I run North on E. boundary of sec. 36.