

Subdivisions of T. 1 N., R. 32 E.

Chains	
	<p>5½ ft. dist. from stone and raised a mound of earth 18 ins. high, 3½ ft. base over it.</p>
54.00	Gulch, course N.W.
75.50	Enter creek bottom.
79.60	<p>To cor. to secs. 23, 24, 25 and 26.</p> <p>Land, rolling.</p> <p>Soil, 1st rate.</p> <p>Scattering cottonwood in bottom.</p> <p>Poor grass and sage brush.</p>
	<p>West on random between secs. 23 and 26.</p> <p style="text-align: right;">Var. 21° East.</p>
40.00	Set temp. ¼ sec. cor.
80.00	<p>To a point, 80 lks. North of old cor.</p> <p>Thence N. 89° 26' East on true line.</p>
5.50	Pendleton and Pilot Rock Wagon Road.
15.00	Summit of ridge, course N. and S.
40.00	<p>Set a stone, 6 x 8 x 10 ins., 7 ins. in the ground for ¼ sec. cor. marked ¼ on N. face, dug pits, 18 x 18 x 12 ins., E and W. 5½ ft. dist. from stone and raised a mound of earth 1½ ft. high, 3½ ft. base over it.</p>
51.00	McKay Creek, runs N.W.
52.00	<p>Intersect U. R. bdy. in center of creek at point, 65 lks. North of true corner. Set stone, 6 x 12 x 14 ins., 10 ins. in the ground on N. bank of creek for witness cor. marked U R. C C W C from which</p> <p style="padding-left: 40px;">A cottonwood, 12 ins. diam., bears S. 50° W., 37 lks. dist. marked U R C C W C B T, and</p> <p style="padding-left: 40px;">A cottonwood, 8 ins. diam., bears N. 35° W., 15 lks. dist. marked U R. C C W C B T.</p>
80.00	<p>To cor. to secs. 23, 24, 25 and 26.</p> <p>Land, rolling.</p> <p>Soil, 1st rate.</p> <p>Cottonwood along creek. Bunch grass.</p>