

## Subdivisions of T. 1 N., R. 32 E.

Chains	
	North on true line between secs. 23 and 24. Var. 21° East.
21.25	Spring branch, 2 lks. wide.
31.50	Leave creek bottom.
39.80	To old $\frac{1}{4}$ sec. cor. Reestablished cor. Set stone, 16 x 10 x 8 ins., 12 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face. Dug pits, 18 x 18 x 12 ins., N and S. from stone, $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base alongside.
71.50	Dry ditch on side of hill, course W.
79.60	Found and reestablished old cor. to secs. 13, 14, 23 and 24. Set stone, 10 x 8 x 8 ins., 6 ins. in the ground marked with 3 notches on S. and 1 on E. edges. Dug pits, 18 x 18 x 12 ins., in each sec. $5\frac{1}{2}$ ft. dist. and raised a mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base alongside in edge of bottom.
	Land, rolling. Soil, 1st rate. Scattering cottonwood along creek. Grass, poor.
	East on random between secs. 13 and 24. Var. 20° 15' East.
40.00	Set temp. $\frac{1}{4}$ sec. cor.
79.71	Intersect Township line, 24 lks. N. of cor. to secs. 13 and 24.
	Thence N. 89° 50' W. on true line. Var. 19° East.
39.85	Set stone, 6 x 7 x 10 ins., 7 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face. Dug pits, 18 x 18 x 12 ins., E. and W. of stone, $5\frac{1}{2}$ ft. dist. and raised a mound of earth 18 ins. high, $3\frac{1}{2}$ ft. base alongside.
60.00	Summit of ridge, course N. and S. Descend.
79.71	To cor. to secs. 13, 14, 23 and 24. Land, rolling.