

Subdivisions of T. 1 N., R. 32 E.

Chains		
	Soil, 1st rate. No timber. Poor bunch grass.	
	East on random between secs. 12 and 13. Var. 20° East.	
40.00	Set temp. $\frac{1}{4}$ sec. cor.	
79.75	Intersect Township line, 1.33 chs. S. of cor. to secs. 12 and 13. Thence S. 89° 03' W. on true line. Var. 21° East.	
20.00	Summit of hill.	+150
35.00	Hollow, course N.W.	
39.87	To old $\frac{1}{4}$ sec. cor. Set a post, 3 ft. long and 3 ins. square, 24 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ S. on N. face and redug pits E. and W. from post, 5 $\frac{1}{2}$ ft. dist. I raised a mound of earth 18 ins. high, 3 $\frac{1}{2}$ ft. base over it.	
50.00	Hollow, course N.W.	
72.00	Wagon Road, course N.E.	
79.75	To cor. to secs. 11, 12, 13 and 14. Land, rolling. Some grass. Soil, 1st rate. No timber. Poor bunch grass.	
	North on true line between secs. 11 and 12. Var. 20° East.	
39.96	Old $\frac{1}{4}$ sec. cor. Reset stone, 7 x 8 x 10 ins., 6 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face. Redug pits, 18 x 18 x 12 ins., N. and S. from stone, 5 $\frac{1}{2}$ ft. dist. and raised a mound of earth, 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base alongside.	
45.50	Trail bears N. W.	
57.30	Summit of hill.	+100
63.00	Gulch or hollow.	-100
79.50	To old cor. Set stone, 12 x 8 x 8 ins., 8 ins. in the ground for cor. to secs. 1, 2, 11 and 12, marked with	