

Subdivisions of T. 1 N., R. 32 E.

Chains		
	<p>5 notches on S. and 1 on E. edges. Dug pits, 18 x 18 x 12 ins. in each sec., $5\frac{1}{2}$ ft. dist. and raised a mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base alongside.</p> <p>Land, rolling.</p> <p>Soil, 1st $\frac{1}{2}$ good, east $\frac{1}{2}$ poor. No timber.</p> <p>Poor bunch grass.</p>	
	<p>East on random between secs. 1 and 12.</p> <p style="text-align: right;">Var. 20° East.</p> <p>40.00 Set temp. $\frac{1}{4}$ sec. cor.</p> <p>80.00 Intersect Township line, 1.31 chs. S. of cor. to secs. 1 and 12.</p> <p>Thence S. 89° 04' W. on true line.</p> <p style="text-align: right;">Var. 20° 45' East.</p>	
	<p>4.25 Road, course S.W.</p> <p>40.00 Old cor. Deposited a charred stake, 12 ins. in the ground, for $\frac{1}{4}$ sec. cor. Dug pits, 18 x 18 x 12 ins., E. and W. of stake, $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it; and in the E. pit drove a stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $\frac{1}{4}$ S. on N. face.</p>	
	<p>56.00 Hollow, course S.</p>	-20
	<p>65.00 " " S.W.</p>	-20
	<p>80.00 To cor. to secs. 1, 2, 11 and 12.</p> <p>Land, rolling.</p> <p>Soil, good. No timber.</p> <p>Poor bunch grass.</p>	
	<p>North on random between secs. 1 and 2.</p> <p style="text-align: right;">Var. 20° East.</p> <p>40.00 Set temp. $\frac{1}{4}$ sec. cor.</p> <p>79.80 Intersect Township line, 15 lks. W. of cor. to secs. 1, 2, 35 and 36.</p> <p>Thence S. 06' W. on true line.</p> <p style="text-align: right;">Var. 21° 30' East.</p>	
	<p>4.00 Flat course W.</p>	-100