

Subdivisions of T. 1 N., R. 32 E.

Chains 39.80	Set a stone, 7 x 8 x 9 ins., 6 ins. in the ground, for $\frac{3}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face. Dug pits, 18 x 18 x 12 ins., N. and S. of stone, $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
79.80	To cor. to secs. 1, 2, 11 and 12. Land, rolling. Soil, good. No timber. Scattering bunch grass.
	North between secs. 14 and 15. Beginning at the old $\frac{1}{4}$ sec. cor. between secs. 14 and 15, which is a stone, 12 x 9 x 8 ins., 8 ins. in the ground marked $\frac{1}{4}$ on W. face, with pits, 18 x 18 x 12 ins., N. and S. from stone, $5\frac{1}{2}$ ft. dist. with mound of earth. Thence N. on true line. Var. 21° East.
3.00	Intersect U. R. bdy. and set a stone, 10 x 10 x 12 ins., 8 ins. in the ground for U. R. closing cor. marked U R C C on N. face. Dug pits, 18 x 18 x 12 ins., N., E. and W. of stone, $5\frac{1}{2}$ ft. dist. and raised a mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it.
29.00	Wagon Road, course S.W.
40.00	To old cor. to secs. 10, 11, 14 and 15 which I re-established by setting a stone, 5 x 8 x 12 ins., 8 ins. in the ground with 4 notches on the S. and 2 on E. edges. Dug pits, 18 x 18 x 12 ins., in each sec., $5\frac{1}{2}$ ft. dist. and raised a mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it. Land, rolling. Soil, 1st rate. No timber. Grass, poor.
	East on random between secs. 11 and 14. Var. 20° 15' East.
40.00	Set temp. $\frac{1}{4}$ sec. cor.
79.60	Intersect East bdy., 45 lks. S. of cor. to secs. 11, 12,