

Subdivisions of T. 1 N., R. 32 E.

Chains	
	<p>13 and 14.</p> <p>Thence S. 89° 41' W. on true line.</p> <p style="text-align: center;">Var. 20° East.</p>
15.00	Creek bottom, course N. and S.
36.90	McKay Creek, 50 lks. wide, N.
39.80	<p>Found old $\frac{1}{4}$ sec. cor. post was rotten. Set stone, 7 x 8 x 12 ins., 8 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face from which</p> <p style="padding-left: 40px;">A balm, 12 ins. diam., bears S. 50° W. 33 lks. dist. marked $\frac{1}{4}$ S B T.</p> <p style="padding-left: 40px;">(No other trees within limits.)</p> <p style="padding-left: 40px;">And raised a mound of stone, 18 ins. high, $3\frac{1}{2}$ ft. base.</p>
48.00	Wagon Road and leave creek bottom.
60.25	Pendleton and Pilot Rock Wagon Road.
79.60	To cor. secs. 10, 11, 14 and 15.
	<p>Land, rolling.</p> <p>Soil, 1st rate. No timber.</p> <p>Grass, poor.</p>
	<p>West on random between secs. 10 and 15.</p> <p style="text-align: center;">Var. 20° 30' East.</p>
39.75	<p>To a point, 15 lks. S. of old $\frac{1}{4}$ sec. cor.</p> <p>Thence S. 89° 47' East on true line.</p> <p style="text-align: center;">Var. 20° 30' East.</p>
22.00	<p>Intersect U. R. bdy. and set a stone, 10 x 10 x 10 ins., 7 ins. in the ground for U. R. closing cor. marked U R C C on E. face and raised a mound of stone 2 ft. high, $4\frac{1}{2}$ ft. base over it.</p>
22.50	Leave field, course N. and S.
39.75	To cor. to secs. 10, 11, 14 and 15.
	<p>Land, rolling.</p> <p>Soil, 1st rate. No timber.</p> <p>Poor bunch grass.</p>
	<p>North on true line between secs. 10 and 11.</p> <p style="text-align: center;">Var. 20° 30' East.</p>