

Cemetery in Section 11, T. 1 N., R. 32 E.
 Surveyed by L. E. Wilkes under special instructions-Group No. 29.
 Dated Aug. 20, 1917.

Chains

Survey commence December 7, 1917 and executed with a Young and Sons transit No. 8585 with Smith solar attachment.

For description, test and approval of instrument and methods of measurement, see Book "B" of this Group.

I commence at the $\frac{1}{4}$ cor. between secs. 10 and 11, T. 1 N., R. 32 E., which is a basalt stone, 9 x 5 x 4 ins., 13 ins. in the ground, marked $\frac{1}{4}$ on W. face.

At a point 1 lk. S. of cor.

Set an iron post, 3 ft. long, 2 ins. diam., 24 ins. in the ground, for witness cor. to the $\frac{1}{4}$ sec. cor., with brass cap marked.

01
 WC
 $\frac{1}{4}$
 S10 | S11
 1917

and raise a mound of stone, 3 ft. base, 2 ft. high, W. of cor.

Thence

S. 41° 52' E., through stubblefield.

19.36 To cor. No. 1 of cemetery and place of beginning.

Set an iron post, 3 ft. long, 2 ins. diam., 24 ins. in the ground, for cor. No. 1, with brass cap marked.

COR 1
 CEM
 1917

Thence

East on N. bdy. of cemetery.

1.035 Set an iron post, 3 ft. long, 2 ins. diam., 24 ins. in the ground, for cor. No. 2, with brass cap marked.

COR 2
 CEM
 1917

Thence

South, on E. bdy. of cemetery.

1.455 Set an iron post, 3 ft. long, 2 ins. diam., 24 ins. in