

Base Line through Range 33 East.
 Surveyed by Timothy W. Davenport, contract No. 102.
 Dated July 20, 1863.

Chains		
	Commencing at the S.E. corner of Town No. 1 North R.32 East. Thence East on the South boundary of sec. 31, Town 1 N., R. 33 East. August 6, 1863.	
40.00	Set qr. sec. post on ridge descending North, made mound of earth with charred stake as per instructions.	+50
54.50	Trail, course N.E.	+20
80.00	Set post corner to secs. 31 and 32, made mound of earth, drove charred stake as per instructions. Var. 20°15'E. Soil of this mile is a hard clay dust producing bunch grass.	+30
	East on the South boundary of sec. 32. Var. 20°15'E.	
40.00	Set qr. sec. post in mound of earth with charred stake as per instructions.	+40
45.00	Commence descending.	+10
55.00	Bottom of hollow descending S. to McKay Creek about 20.00 chs. to the South.	-150
80.00	Set post corner to secs. 32 and 33 in mound of rock with charred stake as per instructions on the side of ridge descending to McKay Creek. Var. 21°E. Surface in ridges. Soil, ash clay producing bunch grass.	-200
	East on the South boundary of sec. 33. Var. 21°E.	
5.00	Commence to descend.	
35.00	Bottom of ravine descending to the South.	-150
40.00	Set qr. sec. post in mound of earth as per instructions. Depositing charred stake, etc. August 6, 1863.	+75
51.50	Top of ridge.	+125
58.00	Bottom of Hollow.	-75
80.00	Set post corner to secs. 33 and 34 in mound of earth,	+150