

Base Line through Range 33 East

Chains		
	depositing charred stake as per instructions. Var. 21°10'E. Surface of this mile broken by sharp ridges. Soil, compact clay dust, fine bunch on last $\frac{1}{2}$ mile. First half rocky.	
	East on South boundary of sec. 34. Var. 21°10'E.	
12.00	Top of ridge.	+50
35.00	Bottom of ravine.	-150
40.00	Set qr. sec. post in mound of earth and drove charred stake as per instructions.	+80
54.00	Top of ridge, N. and S.	+100
63.00	Bottom of ravine.	-150
80.00	Set post corner to secs. 34 and 35, made mound of earth and drove charred stake as per instructions. Var. 20°E. Surface broken into sharp ridges. Soil, encumbered with rock producing bunch grass.	
	East on South boundary of sec. 35. Var. 20°E.	
40.00	Set qr. sec. post, mound of earth, drove charred stake as per instructions.	
65.00	Head of ravine.	
80.00	Set post corner to secs. 35 and 36 on top of ridge, made mound of earth, drove charred stake as per instructions.	+250
	Var. 20°45'E. Surface of this mile is broken by sharp ridges descending rapidly to the South to McKays Creek. Soil, unfit for cultivation.	
	East on South boundary of sec. 36. Var. 40°45'E.	
40.00	Set qr. sec. post, made mound of earth, drove charred as per instructions.	-400