

Base Line through Range 33 East

Chains		
50.00	Bottom of ravine and scattering pine timber.	-100
80.00	Set post corner to secs. 31 and 36, Townships 1 North, Ranges 33 and 34 East on the top of a high ridge. Made mound of rock. Var. 20°15'E.	+350
Subdivisions of T. 1 N., R. 33 E. Surveyed by Daniel Chaplin under contract No. 107. Dated September 21, 1864.		
The East boundary of this Township is on the West slope of the Blue Mountains and is very steep and stony "unfit for settlement, cultivation, grazing or timber". I, therefore, commence at corner to secs. 34 and 35 on Base Line and run North between secs. 34 and 35. Ascend hill.		
40.00	Set stone, 18x14x6, for $\frac{1}{4}$ sec. cor.	
80.00	Set stone, 16x12x6, for corner to secs. 34, 35, 26 and 27. Land, steep and stony. Soil, 2nd rate.	+800
North between secs. 26 and 27. Var. 19 $\frac{1}{2}$ °E.		
31.00	Top of hill on West slope of mountain, bears E. and W.; descend.	+400
40.00	Set stone, 16x12x12, for $\frac{1}{4}$ sec. cor.	
80.00	Set stone, 15x15x6, for corner to secs. 22, 23, 26, and 27 Land, steep and stony. Soil, 3rd rate.	-600
North between secs. 22 and 23. Var. 19°E.		
Descend.		
27.00	Foot of hill; ascend hill.	-500
40.00	Set stone, 24x18x3, for $\frac{1}{4}$ sec. cor.	