

Subdivisions of T. 1 N., R. 33 E.

Chains 39.92	Set post for $\frac{1}{4}$ sec. cor. in mound of earth with charred stake, pits &c as per instructions.
79.92	The corner to secs. 19, 20, 29 and 30. Land, level. Soil, 1st rate.
	North between secs. 19 and 20. Var. 19°E.
40.00	Set stone, 12x8x6.
80.00	Set post for corner to secs. 17, 18, 19 and 20 in mound of earth with charred stake, pits &c as per instructions. Land, level. Soil, 1st rate.
	East on a random line between secs. 17 and 20.
40.00	Set post for temporary $\frac{1}{4}$ sec. cor.
80.00	Intersect N. and S. line at corner to secs. 16, 17, 20 and 21, from which I run West on a true line between secs. 17 and 20.
40.00	Set post for $\frac{1}{4}$ sec. cor. in mound of earth with charred stake, pits &c as per instructions.
80.00	The corner to secs. 17, 18, 19 and 20. Land, level. Soil, 1st rate.
	West on a random line between secs. 18 and 19
40.00	Set temporary $\frac{1}{4}$ sec. cor.
79.68	Intersect West boundary, 30 South of corner to secs. 18 and 19, from which I run S.89°47'E. on a true line between secs. 18 and 19.
39.68	Set stone, 12x10x7, for $\frac{1}{4}$ sec. cor.
79.68	The corner to secs. 17, 18, 19 and 20. Land, level. Soil, 1st rate.