

Subdivisions, T. 1 N., R. 33 E.

Chains	General Description	
	<p>The quality of the land in the Western portion of this Township is level and 1st rate soil being immediately along the base of the Blue Mountains. The eastern portion is steep and stony. Mountains unfit for settlement, grazing or timber and is unsurveyed. There is no timber in this Township. There is plenty of water in numerous springs in different portions of the Township.</p>	
	<p>Exterior Lines of T. 1 N., R. 33 E. Surveyed by Z.F. Moody under contract No. 145. Dated April 23, 1871. (East Boundary)</p>	
	<p>Begin at the South East cor. of T. 1 N., R. 33 East Willamette Meridian, I run North on East boundary sec. 36. Var. 20°30' East.</p>	
40.00	Set basalt stone, 15x14x10, for $\frac{1}{4}$ section corner.	
80.00	<p>Set basalt stone, 18x12x12, for corner to secs. 25, 36, 30 and 31.</p>	
	<p>Land, hilly. Soil, good, 2nd rate. Grass, good.</p>	
	<p>North on East boundary sec. 25. Var. 22° East.</p>	
10.00	Bottom of canyon.	-150
25.00	Top of hill.	+100
40.00	Set basalt stone, 24x14x12, $\frac{1}{4}$ section corner.	
80.00	<p>Set basalt stone, 20x18x12, corner to secs. 24, 25, 19 and 30.</p>	
	<p>Land, hilly. Soil, 2nd rate. Grass, good.</p>	
	<p>North on East boundary of sec. 24. Var. 21°30' East.</p>	