

East Boundary of T. 1 N., R. 33 E.

| | | |
|--------|--|------|
| Chains | | |
| 35.00 | Brook, 4 lks. wide, flows NW. | |
| 40.00 | Set post in stone mound for $\frac{1}{4}$ section corner. | |
| 80.00 | Set basalt stone, 14x14x12, for corner to secs. 24, 13, 18 and 19. | |
| | Land, hilly. | |
| | Soil, 2nd rate | |
| | Grass, good. | |
| | North on East boundary of sec. 13. | |
| | Var. 21° East. | |
| 27.00 | Brook, 4 lks. wide, flows N.W. | |
| 40.00 | Set basalt stone, 16x12x10, for $\frac{1}{4}$ section corner. | +75 |
| 67.00 | Brook, 5 lks. wide, flows N.W. | -40 |
| 80.00 | Set basalt stone, 16x16x10, for corner. | |
| | North on East boundary of sec. 12. | |
| | Var. 21° E. | |
| 18.00 | Brook, 6 lks. wide, flows East. | -100 |
| 40.00 | Set basalt stone, 14x14x12, for $\frac{1}{4}$ sec. corner. | +75 |
| 80.00 | Set basalt stone, 16x14x12, for corner to secs. 1, 12, 6 and 7. | |
| | Land, hilly. | |
| | Soil, 2nd rate. | |
| | Grass, good. | |
| | North on East boundary of sec. 1. | |
| | Var. 21°30' East. | |
| 40.00 | Set basalt stone, 16x14x12, for $\frac{1}{4}$ section corner. | -75 |
| 80.00 | Set basalt stone, 18x16x14, for corner to Townships 1 and 2 North, Ranges 33 and 34 East Willamette Meridian. | |
| | Land, hilly. | |
| | Soil, 2nd rate. | |
| | Grass, good. | |
| | May 1, 1871. | |