

Subdivisions of T. 1 N., R 33 E.

Chains	North between secs. 10 and 11. Var. 18°30'E.	
40.00	Set post and made earth mound for $\frac{1}{4}$ sec. corner.	
80.00	Set post and made mound of earth for $\frac{1}{4}$ sec. corner. Land, sloping North West. Soil, 2nd rate. Grass, good.	-650
	North on random between secs. 2 and 3. Var. 19°East.	
40.00	Set temporary $\frac{1}{4}$ sec. corner.	
80.54	Intersected North boundary, 48 lks. E. of cor. S.00°20'E. on true line.	
40.54	Set post and stone mound for $\frac{1}{4}$ sec. corner.	
79.00	Tudie Willow, 8 lks. wide, flows N.E.	
80.54	To corner. Land, level. Soil, 1st rate. Grass, good.	
	May 3, 1871.	
	North between secs. 35 and 36. Var. 19°30'E.	
40.00	Set stone, 14x12 x12, for $\frac{1}{4}$ S. cor.	
80.00	Set stone, 20x14x8, for corner to secs. 35, 36, 25 and 26. Land, hilly. Soil, 2nd rate. Grass, good.	+450
	East on random between secs. 25 and 36. Var. 20°E.	
40.00	Set temporary $\frac{1}{4}$ sec. corner.	
80.14	Intersected N. and S. line, 10 lks. S. of corner. S.89°56'W. on true line.	
40.07	Set stone, 16x12x12, for $\frac{1}{4}$ sec. cor.	-350
80.14	To corner.	+400