

## Subdivisions of T. 1 N., R. 33 E.

Chains	Land, hilly. Soil, 2nd rate. Some good grass.	
	W. on random between sections 26 and 35.	
40.00	Set temporary $\frac{1}{4}$ sec. corner.	
80.10	Intersected N. and S. line, 12 lks. N. of corner. N.89°55' East on true line.	
40.05	Set basalt stone, 18x14x10, for $\frac{1}{4}$ section corner.	-600
80.10	To corner.	+540
	Land, hilly. Soil, 2nd rate.	
	North between secs. 25 and 26.	
38.00	Top of bluff.	+240
40.00	Set stone, 14x12x10, for $\frac{1}{4}$ sec. corner.	
80.00	Set basalt stone, 18x14x8, for corner to secs. 25, 26, 23 and 24.	-350
	Land, hilly. Soil, 2nd rate. Some grass.	
	East on random between secs. 24 and 25. Var. 21° East.	
40.00	Set temporary $\frac{1}{4}$ section corner.	
80.18	Intersected N. and S. line, 14 lks. S. of cor. S.89°54'W. on true line.	
40.09	Set basalt stone, 14x14x10, for $\frac{1}{4}$ section corner.	-500
80.18	To Corner.	
	Land, hilly. Soil, 2nd rate.	
	West on random between secs, 23 and 26.	
40.00	Set temporary $\frac{1}{4}$ sec. corner.	
80.20	Intersected N. and S. line, 12 S. of corner. S.89°55'E. on true line.	
40.10	Set basalt stone, 16x14x7, for $\frac{1}{4}$ sec. corner.	+500