

Subdivisions of T. 1 N., R. 33 E.

Chains		
	North between secs. 13 and 14.	
40.00	Set stone, 15x12x4, for $\frac{1}{4}$ S. corner.	-400
55.50	Brook, 4 lks. wide, flows N.W.	-50
80.00	Set stone, 17x16x5, for corner to secs. 13, 14, 11 and 12.	+500
	Land, hilly.	
	Soil, 2nd rate.	
	Grass, good.	
	East on random between secs. 12 and 13.	
	Var. 21° East.	
40.00	Set temporary $\frac{1}{4}$ sec. post.	
80.14	Intersected N. and S. line, 15 lks. N. of cor. N.89°54'W. on true line.	
40.07	Set stone, 16x12x10, for $\frac{1}{4}$ sec. cor.	-375
40.75	Brook, 4 lks. wide, flows N.W.	
80.14	To corner.	+400
	Land, hilly.	
	Soil, 2nd rate.	
	Grass, good.	
	West on random between secs. 11 and 14.	
40.00	Set temporary $\frac{1}{4}$ section corner.	
80.00	Intersected N. and S. line, 10 lks. S. of cor. S.89°56'E. on true line.	
40.00	Set basalt stone, 14x12x8, for $\frac{1}{4}$ sec. corner.	
80.00	To corner.	+375
	Land, hilly.	
	Soil, 2nd rate.	
	Grass, good.	
	North between secs. 11 and 12.	
11.55	Tudie Willow, 5 lks., flows N.W.	-100
40.00	Set stone, 14x12x10, for $\frac{1}{4}$ S. corner.	+150
80.00	Set stone, 18x16x14, for corner to secs. 1, 2, 11 and 12.	
	Land, hilly.	
	Soil, 2nd rate.	