

Subdivisions of T. 1 N., R. 33 E.

Chains	Land, hilly. Soil, good, 2nd rate. First rate quality of grass.	
	East on random between secs. 27 and 34. Var. 20°E.	
40.00	Set temporary $\frac{1}{4}$ sec. corner.	
79.85	Intersected N. and S. line, 40 lks. N. of cor. N.89°43'W. on true line.	
39.97	Set stone, 20x15x9, for $\frac{1}{4}$ sec. cor.	
65.00	Foot of hill.	-500
79.85	To corner. Land, hilly, sloping to the West. Soil, 2nd rate with fine growth of nutritious bunch grass.	
	North between secs. 27 and 28.	
40.00	Set post and made mound of earth for $\frac{1}{4}$ sec. cor.	
80.00	Set post and made mound of earth for cor. to secs. 27, 28, 21 and 22. Land, hilly. Soil, 2nd rate. Soil produces fine grass.	
	East on random between secs. 22 and 27. Var. 19°45'E.	
40.00	Set temporary $\frac{1}{4}$ sec. corner.	
79.72	Intersected N. and S. line, 60 lks. N. of cor. N.89°34'W. on true line.	
39.86	Set post and made mound of stone for $\frac{1}{4}$ sec. corner.	
79.72	To corner. Land, hilly and sloping West. Soil, good, 2nd rate. Good grass.	
	North between secs. 21 and 22.	
40.00	Set stone, 14x12x10, for $\frac{1}{4}$ S. cor.	
80.00	Set post and made mound of earth for cor. to secs. 21, 22, 15 and 16.	