

Subdivisions of T. 1 N., R. 33 E.

Chains	Land, hilly. Soil, 2nd rate, producing fine grass.	
	East on random between secs. 15 and 22. Var. 20°E.	
40.00	Set temporary $\frac{1}{4}$ sec. cor.	
79.80	Intersected N. and S. line, 58 lks. N. of cor. N.89°35'W. on true line.	
39.90	Set stone, 20x15x12, for $\frac{1}{4}$ S. cor.	
79.80	To corner.	
	Land, hilly. Soil, 2nd rate with fine grass.	
	North between secs. 15 and 16.	
26.00	Foot of hill.	-150
40.00	Set post and made mound of earth for $\frac{1}{4}$ sec. corner.	
80.00	Set post and made earth mound for cor. to secs. 15, 16, 9 and 10.	
	Land, generally level.	
	The soil, 1st rate, with good grass.	
	East on random between secs. 10 and 15.	
	Var. 20°E.	
40.00	Set temporary $\frac{1}{4}$ sec. cor.	
80.14	Intersected N. and S. line, 30 lks. N. of cor. N.89°47'W. on true line.	
37.00	Foot of hill.	-350
40.07	Set stone, 18x10x10, for $\frac{1}{4}$ S. cor.	
80.14	To corner.	
	Land, generally rolling.	
	Soil, 1st rate. Good grass.	
	North between secs. 9 and 10.	
40.00	Set post and made mound of earth for $\frac{1}{4}$ sec. cor.	
80.00	Set post and made earth mound for cor. to secs. 9, 10, 3 and 4.	