

## Subdivisions of T. 1 N., R. 33 E.

Chains	Land, generally rolling. Soil, very good with fine grass.
	North between secs. 28 and 29.
40.00	Set post and made mound of earth for $\frac{1}{4}$ sec. corner.
80.00	Set post and made mound of earth for cor. to secs. 28, 29, 20 and 21.
	Land, level. Soil, 1st rate. Good grass.
	November 4, 1871.
	East on random between secs. 21 and 28. Var. 20°30'E.
40.00	Set temporary $\frac{1}{4}$ sec. corner.
80.00	Intersected N. and S. line, 20 lks. S. of cor. S. 89°51'W. on true line.
40.00	Set post and made mound of earth for $\frac{1}{4}$ sec. corner.
80.00	To the cor. to secs. 28, 29, 20 and 21.
	Land, level. Soil, 1st rate. Good grass.
	North between secs. 20 and 21.
40.00	Set post and made earth mound for $\frac{1}{4}$ S. cor.
80.00	Set post and made mound of earth for cor. to secs. 20, 21, 16 and 17.
	Land, level. Soil, 1st rate.
	East on random between secs. 16 and 21. Var. 21°E.
40.00	Set temporary $\frac{1}{4}$ S. cor.
79.94	Intersected N. and S. line, 14 lks. S. of cor. S. 89°54'W. on true line.
39.97	Set post and made mound of earth for $\frac{1}{4}$ S. cor.
79.94	To corner. Land, level. Soil, 1st rate. Good grass.