

Subdivisions of T. 1 N., R. 33 E.

Chains	Land, level. Soil, 1st rate. Good grass.
40.00	East on random between secs. 20 and 29. Var. 19°30'E.
79.84	Set temporary $\frac{1}{4}$ S. cor. Intersected N. and S. line, 14 lks. S. of cor. S.89°54'W. on true line.
39.92	Set post and made mound of earth for $\frac{1}{4}$ S. cor.
79.84	To corner. Land, level. Soil, good. Excellent grass.
40.00	West on random between secs. 19 and 30. Set temporary $\frac{1}{4}$ S. cor.
79.88	Intersected N. and S. line, 12 lks. N. of cor. N.89°55'E. on true line.
39.88	Set post and made mound of earth for $\frac{1}{4}$ S. cor.
79.88	To cor. Land, level. Soil, 1st rate. Good grass.
	Nov. 6, 1871.
40.00	North between secs. 19 and 20. Set post and made mound of earth for $\frac{1}{4}$ sec. cor.
80.00	Set post and made mound of earth for cor. to secs. 19, 20, 17 and 18. Land, level. Soil, 1st rate. Good grass.
40.00	East on random between secs. 17 and 20. Var. 19°45'E. Set temporary $\frac{1}{4}$ S. cor.
80.10	Intersected N. and S. line, 16 lks. S. of cor. S.89° 53'W. on true line.