

Subdivisions of T. 1 N., R. 33 E.

Chains 39.78	Set post and made mound of earth for $\frac{1}{4}$ S. cor.	
79.78	To cor. Land, level. Soil, 1st rate. Good grass. Nov. 7, 1871.	
Base Line of T. 1 N., R. 33 E. Surveyed by Currin and Noland under special contract. Dated May 4, 1887.		
Commencing at cor. to Tps. 1 N., Rgs. 32 and 33 E. I ran East on random on S. bdy. of T. 1 N., R. 33 E. Var. 20° East.		
Set temporary sec. and $\frac{1}{4}$ sec. cors. at every 40 and 80 chains and at 5 miles and 78.50 chains a point 126 lks. S. of cor. to Tps. 1 N., Rgs. 33 and 34 E., which is an old mound of stone, post having disappeared. This cor. I reestablished setting a basalt stone, 18x12x10 ins., 12 ins. in the ground for cor. to Tps. 1 N., Rs. 33 and 34 East marked S.C. with 6 notches on N.E. and S. edges and raised mound of stone 2 ft. high, 4 $\frac{1}{2}$ ft. base over it. This cor. sets our Summit of ridge sloping South. †1000		
Thence S. 89°51'W. on true line, S. bdy. sec. 36. Var. 21 $\frac{3}{4}$ ° East.		
2.00	Begin descent.	
30.00	Canyon, course S.E. Ascend.	-500
40.00	Set post, 3 ft. long, 3 ins. square, 24 ins. in the ground for $\frac{1}{4}$ sec. cor. marked S C $\frac{1}{4}$ S on N. face. Redug old pits, 18x18x12 ins., E. and W. of post, 5 $\frac{1}{2}$ ft. dist. and raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it.	+250
80.00	Set basalt stone, 12x12x10 ins., 8 ins. in the ground for cor. to secs. 35 and 36, T. 1 N., R. 33 E. marked S C with 1 notch on E. and 5 notches on W. edges and raised mound of stone 2 ft. high, 4 $\frac{1}{2}$ ft. base over it. Pits impracticable. Land, mountainous, rough. 80 chs. Soil, 2nd rate, rocky.	