

East Boundary of T. 1 N., R. 33 E.

| | | |
|--------|--|------|
| Chains | North on E. bdy. of sec. 24. Var. 20°E. | |
| 27.50 | Leave table land. | |
| 36.50 | Canyon, course W. | -300 |
| 40.00 | Set a basalt stone, 12x10x8 ins., 8 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face. Raised md. of stone alongside. Pits impracticable. | +100 |
| 57.50 | Gulch, course W. | -100 |
| 80.00 | Set basalt stone, 20x12x12 ins., 15 ins. in the ground for cor. to secs. 13, 18, 19 and 24 marked 3 notches on N. and S. edges. Raised md. of stone alongside. Pits impracticable. Land, mountainous. 52.50 chs. Soil on table land, 1st rate with fine bunch grass and sun flower balance 3rd rate; poor grass. No timber. | +400 |
| | North on E. bdy. of sec. 13. Var. 21°E. | |
| 6.00 | Trail on ridge, course N.E. | +100 |
| 10.00 | Descend. | |
| 23.25 | Canyon, course SW. | -300 |
| 40.00 | Set a basalt stone, 12x8x6 ins., 8 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face. Raised stone mound alongside. Pits impracticable. | |
| 45.00 | Summit. | +250 |
| 67.80 | Canyon, spring branch, 2 lks. wide, course W. | -300 |
| 80.00 | Set a basalt stone, 20x16x10 ins., 15 ins. in the ground for cor. to secs. 12, 13, 18 and 7 marked 4 notches on S. and 2 on N. edges. Raised md. of stone alongside. Pits impracticable. Land, mountainous. 80 chs. Soil, rocky, 4th rate. No timber. Poor grass. | |