

East Boundary of T. 1 N., R. 33 E.

Chains	North on E. bdy. of sec. 12. Var. 21°45'E.	
17.75	Canyon, course W.	-200
40.00	Table land. Set a basalt stone, 20x9x8 ins., 15 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face. Raised a md. of stone alongside. Pits impracticable.	+400
54.00	Wagon road, course E. and W.	
80.00	Set a basalt stone, 18x10x8 ins., 12 ins. in the ground for cor. to secs. 1, 6, 7 and 12, marked 5 notches on S. and 1 on N. edges. Raised a mound of stone alongside. Pits impracticable. Land, mountainous. 40 chs. Soil, 3rd rate. Good bunch grass.	
	North on E. bdy. S. 1. Var. 20°15'E.	
	Leave Table land.	
40.00	Set a basalt stone, 18x12x12 ins., 12 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face. Raised mound of stone alongside. Pits impracticable.	
41.00	Gulch, course NW.	-200
70.00	Summit.	+200
80.00	Set a basalt stone, 16x12x8 ins., 11 ins. in the ground for cor. to Tps. 1 and 2 N., R. 33 and 34 East. Marked 6 notches on N., S., E. and W. edges. Dug pits, 24x18x12, on each line N., S., E. and W. of cor., 6 ft. dist. Raised earth mound 2 $\frac{1}{2}$ ft. high, 5 ft. base alongside. Land, mountainous. 80 chs. Soil, rocky, 3rd rate on S. hillsides, 1st rate on N. sides and benches. Good bunch grass. No timber. August 3, 1887.	