

Subdivisions of T. 1 N., R. 33 E.

| | | |
|--------|--|-------|
| Chains | stone $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it. Pits impracticable. | |
| 45.00 | Gulch, SE. Ascend. | -200 |
| 79.00 | Summit ridge, S.W. | +800 |
| 79.85 | Cor. to secs. 25, 26, 35 and 36. Land, rough and mountainous. 79.85 chs. Soil, good on N. hillsides. Timber, pine in canyon. Fine bunch grass. | |
| | North between secs. 25 and 26. Var. 14° East. Ascend. | |
| 35.00 | Summit of Table Mountain. | +1800 |
| 40.00 | Set basalt stone, $14 \times 12 \times 10$ ins., 9 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face, and raised mound of stone $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it. Pits impracticable. Descend gradually. | |
| 80.00 | Set basalt stone, $14 \times 14 \times 12$ ins., 9 ins. in the ground for cor. to secs. 23, 24, 25 and 26, marked with 2 notches on S. and 1 notch on E. edges and raised mound of stone 2 ft. high, $4\frac{1}{2}$ ft. base over it. Pits impracticable. Land, high and mountainous. 80 chs. Soil, 1st rate on top of mountain. Fine bunch grass and wild sunflower. | |
| | East on random between secs. 24 and 25. Var. 23° E. | |
| 40.00 | Set temporary $\frac{1}{4}$ sec. cor. and at | |
| 80.10 | Intersect E. bdy. Township, 35 lks. S. of cor. to secs. 24, 25, 19 and 30. Thence S. $89^{\circ}45'$ W. on true line between secs. 24 and 25. Var. $21^{\circ}20'$ East. | |
| 13.00 | Wood road, N.W. | |