

Subdivisions of T. 1 N., R. 33 E.

| | | |
|--------|--|------|
| Chains | West on true line between secs. 13 and 24 Var. 21° East. | |
| 16.00 | Bluff rock, 15 ft. high, N. and S. | |
| 31.00 | Branch, 5 lks. wide, runs N. | -500 |
| 40.07 | Set basalt stone, 9x8x7 ins., 6 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face and raised mound of earth and stone, $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it. Pits impracticable. | |
| 44.00 | Summit, ridge N.W. | +350 |
| 50.00 | Canyon, N.W. | -300 |
| 68.00 | Summit, ridge N. Descend. | +700 |
| 80.15 | Cor. to secs. 13, 14, 23 and 24. Land, very rough and mountainous. 80.15 chs. Soil, 3rd rate and rocky. Good grass. | |
| | North between secs. 13 and 14. Var. 23° East. | |
| 33.00 | Spring, branch N.W. | |
| 40.00 | Set basalt stone, 9x8x7 ins., 6 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face and raised mound of stone $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it. Pits impracticable. | |
| 45.00 | Top of hill or ridge, W. Descend. | +800 |
| 60.25 | Gulch, W. | -300 |
| 65.00 | Summit, ridge N.W. | +500 |
| 80.00 | Set basalt stone, 12x12x8 ins., 8 ins. in the ground for cor. to secs. 11, 12, 13 and 14 marked with 4 notches on S. and 1 notch on E. edges. Dug pits, 18x18x12 ins., in each secs. $5\frac{1}{2}$ ft. dist. and raised mound of earth $2\frac{1}{2}$ ft. high, $4\frac{1}{2}$ ft. base over it. Land, rough and mountainous. 80 chs. Soil, 3rd rate and rocky. Good grass. | |
| | July 30, 1887. | |