

Subdivisions of T. 1 N., R. 33 E.

Chains	East on random between secs. 12 and 13. Var. 21° East.	
40.00	Set temporary $\frac{1}{4}$ sec. cor. and at	
79.75	Intersect E. bdy. Township, 24 lks. N. of cor. to secs. 12, 13, 7 and 18. Thence N.89°50'W. on true line between secs. 12 and 13. Var. 21 $\frac{1}{4}$ ° East.	
	Descend sloping ridge.	
20.75	Canyon, S.W.	-500
24.75	Gulch, S.	-25
39.87	Set basalt stone, 8x8x8 ins., 6 ins. in the ground marked $\frac{1}{4}$ on N. face for $\frac{1}{4}$ sec. cor., dug pits, 18x18x12 ins., E. and W. of stone, 5 $\frac{1}{2}$ ft. dist., raised mound of earth and shell rock 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it.	+200
57.00	Canyon, N.W. Ascend sloping ridge.	-250
79.75	Cor. to secs. 11, 12, 13 and 14. Land, rough and mountainous. 79.75 chs. Soil, rocky, 4th rate. Some bunch grass.	
	North between secs. 11 and 12. Var. 21° East.	
	Descend.	
10.00	Spring branch, 5 lks., N.W. Ascend steep mountain side.	-300
40.00	Set basalt stone, 20x16x12 ins., 15 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face and raised mound of stone 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it. Pits impracticable.	
45.00	Top mountain or ridge, W. Descend.	+800
60.25	Gulch, W.	-300
74.50	Canyon, S.W. Ascend.	-500
80.00	Set basalt stone 14x10x5 ins., 8 ins. in the ground for cor. to secs. 1, 2, 11 and 12 marked with 5 notches	