

## Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 28
60.00	<p>To the <math>\frac{1}{4}</math> sec. corner between secs. 28 and 29.  Land, mountainous.  Soil, 1st rate on N. hillside, rocky on S. hillside.  Good bunch grass.</p>
59.85	<p>From the <math>\frac{1}{16}</math> sec. corner, 20 chs. N. of <math>\frac{1}{4}</math> sec. corner between secs. 28 and 29.  Thence I run  S.89°45'E. on random line in N.<math>\frac{1}{2}</math> of sec. 28.  Var. 20°E.  Setting temporary corners at 20 and 40 chains, and at  Intersect the N. and S. line, 20 lks. S. of <math>\frac{1}{16}</math> sec. corner in sec. 28.  Thence I run  N.89°54'W. on true line in N.<math>\frac{1}{2}</math> of sec. 28.  Var. 19°East.</p>
17.50	Road, course N.E.
19.95	<p>Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for <math>\frac{1}{16}</math> sec. corner marked <math>\frac{1}{16}</math> on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5<math>\frac{1}{2}</math> ft. dist., and raised a mound of earth 1<math>\frac{1}{2}</math> ft. high, 3<math>\frac{1}{2}</math> ft. base over it.</p>
38.50	Road, course N.E.
39.90	<p>Set basalt stone, 10x8x7 ins., 7 ins. in the ground, for <math>\frac{1}{16}</math> sec. corner marked <math>\frac{1}{16}</math> on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5<math>\frac{1}{2}</math> ft. dist., and raised a mound of earth 1<math>\frac{1}{2}</math> ft. high, 3<math>\frac{1}{2}</math> ft. base alongside.</p>
59.85	<p>To the <math>\frac{1}{16}</math> corner, 20 chs. N. of <math>\frac{1}{4}</math> sec. corner between secs. 28 and 29.  Land, mountainous.  Soil, 1st rate.  Good grass.</p>