

Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 29
	West on true line between secs. 29 and 32. Var. 21°30' East.
9.50	Road, course S.W.
20.03	Set stone, 12x8x7 ins., 8 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.
40.06	To the ¼ sec. corner, which is a basalt stone, 12x7x8 ins., 8 ins. in the ground, marked ¼ on N. face. Pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., mound of earth 1½ ft. high, 3½ ft. base over it.
48.00	Gulch, course S.W.
60.09	Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, and raised a mound of earth 1½ ft. high, 3½ ft. base over it.
80.12	To the corner to secs. 29, 30, 31 and 32, which is a stone, 10x8x8 ins., 6 ins. in the ground, marked with 1 notch on S. and 5 notches on E. edges, with pits, 18x18x12 ins., in each sec., 5½ ft. dist. and mound of earth 2 ft. high, 4½ ft. base over it.
	Land, rolling.
	Soil, 2nd rate.
	Vegetation scarce.
	North between secs. 29 and 30. Var. 20° E.
20.00	Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.
40.00	To the ¼ sec. corner, which is a basalt stone, 14x10x4 ins., 8 ins. in the ground, marked ¼ on W. face. Pits, 18x18x12 ins., N. and S. of stone, 5½ ft. dist., and mound of earth 1½ ft. high, 3½ ft. base over it.