

Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 29
57.85	Creek, 5 lks. wide, course W.
60.00	Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.
80.00	To corner to secs. 19, 20, 29 and 30. Land, rolling. Soil, 2nd or 3rd rate. Very little grass and grasshoppers.
From the 1/16 sec. corner, 20 chs. N. of the corner to secs. 29, 30, 31 and 32.	
I run	
East on random line through the S.½ of sec. 29.	
Var. 20°30'E.	
Setting temporary corner at 20, 40 and 60 chains, and at	
80.00	Intersect the N. and S. line, 15 lks. N. of 1/16 sec. corner between secs. 28 and 29.
Thence I run	
N.89°54'W. on true line through the S.½ of sec. 29.	
Var. 21°E.	
18.00	Creek, 5 lks. wide, course N.80°W..
20.00	Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.
40.00	Set basalt stone, 10x8x6 ins., 7 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.
60.00	Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.