

Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 30
20.00	Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.
40.00	To the old ¼ sec. corner, which is a basalt stone, 18x10x10 ins., 12 ins. in the ground, marked ¼ on N. face. Pits, E. and W. of stone, 5½ ft. dist., and mound of earth 1½ ft. high, 3½ ft. base over it.
60.00	Set basalt stone, 11x8x7 ins., 7 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.
78.14	Intersect West boundary of Tp. at closing corner to secs. 30 and 31, T. 1 N., R. 33 E., which is a basalt stone, 9x8x7 ins., 6 ins. in the ground, marked C C on E. face with 1 notch on S. and 5 notches on N. faces, with pits, 18x18x12 ins., N., E. and S. of stone, 5½ ft. dist., and mound of earth 2 ft. high, 4½ ft. base over it. I marked stone D R on E. face. Land, rolling. Soil, very ashy Very little grass.
	From the corner to secs. 19 and 30 on the West bdy. of Tp. I run South on true line on the West bdy. of sec. 30. Var. 20° E.
1.30	To the corner of secs. 24 and 25, T. 1 N., R. 32 E., which is a basalt stone, 14x10x8 ins., 10 ins. in the ground, marked 2 notches on S. and 4 notches on N. edges. Pits, 18x18x12 ins., in each sec. 5½ ft. dist., and mound of earth 2 ft. high, 4½ ft. base alongside. I marked