

Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 30.
	stone D R on E. face.
20.00	Deposited charred stake, 12 ins. in the ground, for 1/16 sec. corner. Dug pits, 18x18x12 ins., N. and S. of corner, 5½ ft. dist., and raised mound of earth 1½ ft. high, 3½ ft. base over it. In N. pit drove a stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on W. face and D R on E. face.
40.00	Set a basalt stone, 10x8x6 ins., 6 ins. in the ground, for ¼ sec. corner marked ¼ on W. and D R on the E. face. Dug pits, 18x18x12 ins., N. and S. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.
41.15	To the ¼ sec. corner on E. bdy. of sec. 25, T. 1 N., R. 32 E., which is a basalt stone, 12x10x10 ins., 8 ins. in the ground, marked ¼ on W. face. Pits, 18x18x12 ins., N. and S. of stone, 5½ ft. dist., and mound of earth alongside. I marked stone D R on E. face.
60.00	Set basalt stone, 10x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on W. and D R on E. face. Dug pits, 18x18x12 ins., N. and S. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.
80.00	To the closing corner to secs. 30 and 31. Land, rolling. Soil, ashy. Very little vegetation.
	From the 1/16 sec. corner, 20 chs. N. of corner to secs. 29, 30, 31 and 32.
	I run
	West on random line through S½ of sec. 30.
	Var. 20° East.
	Setting temporary corners at 20, 40 and 60 chs., and at
78.20	Intersect the West boundary of Township, 6 lks. South of 1/16 sec. cor. on W. bdy. of sec.30.