

Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 30
58.25	Set a basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.
66.75	Creek, 5 lks. wide, course N.W.
78.25	To the 1/16 sec. corner between secs. 29 and 30. Land, mostly level. Soil, 2nd rate. Weeds.
Sec. 31	
From the closing corner of secs. 30 and 31 on West bdy. of Tp.	
I run	
South on true line on W. bdy. of sec. 31.	
Var. 20°30' East.	
1.22	To the old corner to secs. 25 and 36, T. 1 N., R. 32 E., which is a basalt stone, 16x12x8 ins., 11 ins. in the ground, marked 1 notch on S. and 5 notches on N. edges. Pits in each sec., 18x18x12 ins., 5½ ft. dist., and mound of earth 2 ft. high, 4½ ft. base alongside. I marked stone D R on E. face.
9.00	Trail, course S.W.
20.00	Set a basalt stone, 10x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on W. face and D R on E. face. Dug pits, 18x18x12 ins., N. and S. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.
36.00	Gulch, course West.
40.00	Set basalt stone, 9x8x7 ins., 6 ins. in the ground for ¼ sec. corner marked ¼ on W. and D R on E. faces. Dug pits, 18x18x12 ins., N. and S. of stone, 5½ ft. dist., raised a mound of earth 1½ ft. high, 3½ ft. base over it.
40.60	To the old ¼ sec. corner on the East bdy. of sec. 36, T. 1 N., R. 32 E., which is a basalt stone, 10x8x6 ins., 7 ins. in the ground, marked ¼ on W. face. Pits,