

Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 31
	18x18x12 ins., N. and S. of stone, 5½ ft. dist., and a mound of earth 1½ ft. high, 3½ ft. base over it. I marked stone D R on E. face.
60.00	Set a basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on W. and D R on E. face. Dug pits, 18x18x12 ins., N. and S. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.
80.00	To the corner to Township 1 N., Ranges 32 and 33 E. in the Base Line, which is a basalt stone, 16x14x10 ins., 11 ins. in the ground marked S C with 6 notches on N., E. and W. edges, and mound of stone over it. I marked stone D R on E. face.
	Land, level.
	Soil, 2nd rate.
	Very little grass.
	From the corner to secs. 31 and 32 on South boundary of Tp., which is a basalt stone, 15x7x6 ins., 10 ins. in the ground, marked S C with 5 notches on E. and 1 notch on W. edges. Pits, 18x18x12 ins., N. E. and W. of stone, 5½ ft. dist., and mound of earth 2 ft. high, 4½ ft. base over it.
	I run
	S.89°51'W. on true line on S. bdy. of sec. 31.
	Var. 18°10'E.
20.00	Set a basalt stone, 10x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.
27.00	Trail, course N.W.
39.00	" " " "
40.00	To the ¼ sec. corner on South bdy. of sec. 31, which is a basalt stone, 10x8x8 ins., 6 ins. in the ground, marked ¼ on N. face. Pits, 18x18x12 ins., E. and W. of stone,