

Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 31
	5½ ft. dist., and mound of earth 1½ ft. high, 3½ ft. base over it.
42.00	Draw, course N.
60.00	Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., and raised mound of earth 1½ ft. high, 3½ ft. base over it.
78.50	To the corner to Township 1 N., Ranges 32 and 33 East. Land, rolling. Soil, 2nd rate. Grass scarce.
	From the corner to secs. 31 and 32 on South bdy. of Tp. I run North between secs. 31 and 32. Var. 18°10' East.
20.00	Set a basalt stone, 12x8x6 ins., 8 ins. in the ground, for 1/16 sec. corner marked 1/16 on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, 5½ ft. dist., raised a mound of earth 1½ ft. high, 3½ ft. base over it.
39.60	Gulch, course N.W.
40.00	To the ¼ sec. corner, which is a basalt stone, 12x10x8 ins., 8 ins. in the ground, marked ¼ on W. face, and mound of stone over it.
60.00	Set a basalt stone, 9x7x8 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, 5½ ft. dist., raised a mound of earth 1½ ft. high, 3½ ft. base over it.
80.00	To the corner of secs. 29, 30, 31 and 32. Land, rolling. Soil, 2nd rate. Weeds and briars.
	From the 1/16 sec. corner, 20 chs. N. of the corner to secs. 31 and 32 on the S. bdy. of Township. I run