

## Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 31
	West on random line through the S. $\frac{1}{2}$ of sec. 31 Var. $17\frac{1}{2}^{\circ}$ E. Setting temporary cors. at every 20, 40 and 60 chains and at
78.35	Intersect the West boundary of Township at $1/16$ sec. corner. Thence I run East on true line through the S. $\frac{1}{2}$ of sec. 31. Var. $20^{\circ}$ E.
10.35	Draw, course N.
14.35	" " "
18.35	Set basalt stone, 10x9x6 ins., 6 ins. in the ground, for $1/16$ sec. corner marked $1/16$ on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, $5\frac{1}{2}$ ft. dist., raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
38.35	Set a basalt stone, 14x9x8 ins., 10 ins. in the ground, for $1/16$ sec. corner marked $1/16$ on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, $5\frac{1}{2}$ ft. dist., raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
58.35	Set a basalt stone, 9x8x7 ins., 6 ins. in the ground, for $1/16$ sec. corner, marked $1/16$ on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, $5\frac{1}{2}$ ft. dist., raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
78.35	To the $1/16$ sec. corner between secs. 30 and 31. Land, level. Soil, 2nd and 3rd rate. No grass.
	From the $\frac{1}{4}$ sec. corner between secs. 31 and 32. I run West on random line through the center of sec. 31. Var. $20^{\circ}$ E. Setting temporary corners at every 20, 40 and 60 chs., and at