

Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 31
78.30	Intersect the West bdy. of Tp., 10 lks. S. of $\frac{1}{4}$ sec. corner on West bdy. of sec. 31.
	Thence I run S.89°56' East on true line through the center of sec. 31. Var. 20°E.
18.30	Set basalt stone, 12x8x7 ins., 8 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face, and raised a mound of stone over it. Pits impracticable.
38.30	Set a basalt stone, 14x9x7 ins., 9 ins., in the ground, for $\frac{1}{4}$ sec. corner marked $\frac{1}{4}$ on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5 $\frac{1}{2}$ ft. dist., and raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it.
48.30	Draw, course N.
58.30	Set a basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5 $\frac{1}{2}$ ft. dist., raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it.
74.30	Gulch, course N.W.
78.30	To the $\frac{1}{4}$ sec. corner between secs. 31 and 32. Land, level. Soil, 2nd and 3rd rate. No grass.
	From the 1/16 sec. corner, 20 chs. N. of $\frac{1}{4}$ sec. cor. between secs. 31 and 32.
	I run West on random line through N. $\frac{1}{2}$ of sec. 31. Var. 20°E.
	Setting temporary corner at every 20, 40 and 60 chains, and at
78.25	Intersect the West bdy. of Tp. at 1/16 section corner on W. bdy. of sec. 31.
	Thence I run East on true line through N. $\frac{1}{2}$ of sec. 31. Var. 19°30'E.
18.25	Set a basalt stone, 9x8x7 ins., 6 ins. in the ground,