

Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 32
	From the corner to secs. 32 and 33 on South bdy. of Township, which is a basalt stone, 18x14x10 ins., 12 ins. in the ground, marked S C, with 4 notches on E. and 2 notches on W. edges, and mound of stone over it.
	I run North between secs. 32 and 33.
	Var. 21°30' East.
10.00	Top of Mt., course E. and W.
20.00	Set stone, 10x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, 5½ ft. dist., and raised mound of earth 1½ ft. high, 3½ ft. base over it.
40.00	The old ¼ sec. corner, which is a basalt stone, 9x8x7 ins., 6 ins. in the ground, marked ¼ on W. face. Pits, 18x18x12 ins., N. and S. of stone, 5½ ft. dist., and mound of earth over it.
48.75	Gulch, course N.W.
60.00	Set a basalt stone, 11x8x5 ins., 7 ins. in the ground for 1/16 sec. corner marked 1/16 on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.
80.00	To corner to secs. 28, 29, 32 and 33. Land, rolling. Soil, 1st rate. Good grass.
	From the 1/16 sec. corner, 20 chs. N. of the cor. to secs. 31 and 32 on the South bdy. of Tp. I run East on random line through S. ½ of sec. 32. Var. 17½° East. Setting temporary cors. at every 20, 40 and 60 chains, and at
79.85	Intersect the N. and S. line, 15 lks. N. of 1/16 sec. corner between secs. 32 and 33.