

Examination of Corners, Exteriors of T. 1 N., R. 33 E.
 Surveyed by Currin and Noland under special contract.
 Dated May 4, 1887.

Going North between secs. 4 and 5 I found cor. secs. 4, 5, 32 and 33. A post, $4\frac{1}{2} \times 4\frac{1}{2} \times 48$ ins., firmly set in ground marked S 33 T 2 N on N.E., S 4 on S.E., S 5 T 1 N R 33 E on S.W., S 32 on N.W. faces, with 4 notches on E. and 2 on W. edges. Pits all right. Mound about blown away.

Going West between secs. 18 and 19.

I found closing cor. secs. 18 and 19 on Township line. A stone, $10 \times 8 \times 7$, marked C C on E. face with 3 notches on N. and S. edges. Pits, E., N. and S., $5\frac{1}{2}$ ft. dist., earth mound around stone partly gone. Pits partially filled.