

Subdivisions of T. 1 N., R. 33 E.

Chains		
33.00	Summit, S.W.	+80
40.00	Set basalt stone, 16x15x14 ins., 10 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
75.50	Gulch, N.W.	-100
79.80	Dry bed creek, W.	
80.00	Set basalt stone, 14x14x14 ins., 8 ins. in the ground for cor. to secs. 27, 28, 33 and 34 marked with 1 notch on S. and 3 notches on E. edges and raised mound of stone 2 ft. high, $4\frac{1}{2}$ ft. base over it. Pits impracticable. Land, rough and hilly. Soil, 2nd rate. Good bunch grass.	
East on random between secs. 27 and 34.		
Var. 20° East.		
40.00	Set temporary $\frac{1}{4}$ sec. cor. and at	
79.63	Intersect N. and S. line, 44 lks. N. of cor. to secs. 26, 27, 34 and 35. Thence N. 89° 41' W. on true line between secs. 27 and 34.	
Var. 19 $\frac{1}{2}$ ° East.		
5.20	Summit hill.	+200
Descend gradual slope.		
39.82	Set stone, 14x8x6 ins., 8 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
79.63	Cor. to secs. 27, 28, 33 and 34. Land, rolling. Soil, 1st rate. Grass good.	
August 1, 1887.		
North between secs. 27 and 28.		
Var. 20° East.		
3.40	Gulch, S.W.	-10
34.00	Summit ridge.	+150