

## Subdivisions of T. 1 N., R. 33 E.

Chains	square, 12 ins. in the ground and marked 1/16 S on N. face.	
79.53	Cor. to secs. 9, 10, 15 and 16. Land, slightly rolling. Soil, good. Very little grass. All cultivable.	
North between secs. 9 and 10. Var. 20° East.		
9.50	Gulch, N.W.	-100
20.00	Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. cor. marked 1/16 on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it.	
40.00	Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for ¼ sec. cor. marked ¼ on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, 5½ ft. dist. and raised mound of earth 1½ ft. high, 3½ ft. base over it.	
54.50	Gulch, N.W.	-20
57.50	Gulch, W.	-20
60.00	Deposited charred stake, 12 ins. in the ground, for 1/16 sec. cor. Dug pits, 18x18x12 ins., N. and S. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S. on W. face.	
80.00	Set basalt stone, 11x8x6 ins., 8 ins. in the ground, for cor. to secs. 3, 4, 9 and 10 marked with 5 notches on S. and 3 notches on E. edges. Dug pits, 18x18x12 ins., in each sec., 5½ ft. dist. and raised mound of earth 2 ft. high, 4½ ft. base over it. Land, level or mostly so. No grass. Soil, 1st rate.	
East on random between secs. 3 and 10. Var. 21° East.		
Set temporary ¼ and 1/16 sec. cors. at 20, 40 and 60 chains and at		