

Subdivisions of T. 1 N., R. 33 E.

Chains	1½ ft. high, 3½ ft. base over it.	
80.00	Set basalt stone, 12x12x12 ins., 8 ins. in the ground, for cor. to secs. 20, 21, 28 and 29, marked with 2 notches on S. and 4 notches on E. edges. Dug pits, 18x18x12 ins., in each sec., 5½ ft. dist., raised mound of earth 2 ft. high, 4½ ft. base over it. Land, rolling. Soil, 1st rate. Very little grass.	
	East on random between secs. 21 and 28. Var. 20½° East.	
40.00	Set temporary ¼ sec. cor. and at	
79.80	Intersect E. bdy, 70 lks. N. of cor. to secs. 21, 22, 27 and 28. Thence N.89°30'W. on true line between secs. 21 and 28. Var. 20° East.	
2.30	Summit hill.	+350
39.90	Set basalt stone, 18x10x6 ins., 12 ins. in the ground, for ¼ sec. cor. marked ¼ on N. face. Dug pits, 18x18x12 ins. E. and W. of stone, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it.	
45.75	Road, N. and S.	
65.00	Gulch, S.W.	
79.80	Cor. to secs. 20, 21, 28 and 29. Land, mostly level. Soil, 1st rate. Very little grass.	
	North between secs. 20 and 21. Var. 20½° East.	
4.00	Dry ditch, W.	-25
30.35	Gulch, W.	-50
40.00	Set basalt stone, 9x8x7 ins., 6 ins. in the ground for ¼ sec. cor. marked ¼ on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it.	