

Subdivisions of T. 1 N., R. 33 E.

Chains 80.00	Set basalt stone, 9x8x7 ins., 6 ins. in the ground for cor. to secs. 16, 17, 20 and 21 marked with 3 notches on S. and 4 notches on E. edges. Dug pits, 18x18x12 ins., in the ground in each sec. 5 $\frac{1}{2}$ ft. dist. and raised mound of earth 2 ft. high, 4 $\frac{1}{2}$ ft. base over it. Land, mostly level. Soil, 1st rate. Bunch grass.	
	East on random between secs. 16 and 21. Var. 23° East.	
40.00	Set temporary $\frac{1}{4}$ sec. cor. and at	
79.72	Intersect E. bdy., 35 lks. N. of cor. to secs. 15, 16, 21 and 22. Thence N.89°45'W. on true line between secs. 16 and 21. Var. 20° East.	
4.35	Wagon road, N. and S.	
10.00	Dry ditch, S.W.	
39.86	Set basalt stone, 9x8x7 ins., 6 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5 $\frac{1}{2}$ ft. dist. and raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it.	
50.00	Wagon road, N. and S.	
75.80	Gulch and ditch dry.	-20
79.72	Cor. to secs. 16, 17, 20 and 21. Land, mostly level. Soil, good. Grass, fair.	
	North between secs. 16 and 17. Var. 23° East.	
40.00	Set basalt stone, 12x10x6 ins., 8 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, 5 $\frac{1}{2}$ ft. dist., raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it.	
72.00	Gulch, N.W.	-10
80.00	Set post, 4 ft. long, 4 ins. square, 24 ins. in the ground for cor. to secs. 8, 9, 16 and 17, marked T 1 N S 9 on	