

## Subdivisions of T. 1 N., R. 33 E.

Chains	North between secs. 8 and 9.
	Var. 20° East.
20.00	Deposited charred stake, 12 ins. in the ground, for 1/16 sec. cor. Dug pits, 18x18x12 ins., N. and S. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in North pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face.
40.00	Deposited charred stake, 12 ins. in the ground, for ¼ sec. cor. Dug pits, 18x18x12 ins., N. and S. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked ¼ S on W. face.
60.00	Deposited charred stake, 12 ins. in the ground, for 1/16 sec. cor. Dug pits, 18x18x12 ins., N. and S. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face.
80.00	Set post, 4 ft. long, 4 ins. square, 24 ins. in the ground, for cor. to secs. 4, 5, 8 and 9 marked T 1 N S 4 on N.E., R 33 E S 9 on S.E., S 8 on S.W. and S 5 on N.W. faces with 5 notches on S. and 4 notches on E. edges. Dug pits, 18x18x12 ins., in each sec. 5½ ft. dist., raised mound of earth 2 ft. high, 4½ ft. base around it.
	Land, level. Grass light.
	Soil, 1st rate.
	East on random between secs. 4 and 9.
	Var. 20½° East.
	Set temporary ¼ and 1/16 sec. cors. and at 20, 40 and 60 chains and at
80.00	Intersect N. and S. line, 42 lks. N. of cor. to secs. 3, 4, 9 and 10. Thence