

Subdivisions of T. 1 N., R. 33 E.

Chains	N. 89° 42' W. on true line between secs. 4 and 9. Var. 21° East.
7.50	Tudie Willow Creek, N., dry.
20.00	Deposited charred stake, 12 ins. in the ground, for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
26.50	Dry ditch, N.
40.00	Deposited charred stake, 12 ins. in the ground, for ¼ sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked ¼ S on N. face.
47.00	Dry ditch, N.
49.00	Wagon road, N.
53.00	Wagon road, N.
60.00	Deposited charred stake, 12 ins. in the ground, for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
80.00	Cor. to secs. 4, 5, 8 and 9. Land, level. Soil, 1st rate. Grass scarce.
	North on random between secs. 4 and 5. Var. 20½° East.
	Set temporary ¼ and 1/16 secs. cors. at 20, 40 and 60 chains and at
76.80	Intersect N. bdy. Township, 112 lks. E. of cor. to secs. 4, 5, 32 and 33. Thence