

Subdivisions of T. 1 N., R. 33 E.

Chains	<p>each sec. $5\frac{1}{2}$ ft. dist. and raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it.</p> <p>Land, rolling. Some grass.</p> <p>Soil, 1st rate.</p>
	<p>East on random between secs. 29 and 32.</p> <p style="text-align: center;">Var. 20° East.</p>
40.00	Set temporary $\frac{1}{2}$ sec. cor. and at
80.12	Intersect N. and S. line at cor. to secs. 28, 29, 32 and 33. Thence
	West on true line between secs. 29 and 32. <p style="text-align: center;">Var. $21\frac{1}{2}^{\circ}$ E.</p>
10.50	Trail, N. and S.
40.06	Set basalt stone, 12x8x7 ins., 8 ins. in the ground, for $\frac{1}{2}$ sec. cor. Dug pits, 18x18x12 ins., E. and W. of stone, $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
48.00	Dry ditch in gulch, S.W.
80.12	Cor. to secs. 29, 30, 31 and 32. <p>Land, rolling. Some grass.</p> <p>Soil, 2nd rate consisting of a kind of white clay or hard pan.</p>
	West on true line between secs. 30 and 31. <p style="text-align: center;">Var. 20° East.</p>
40.00	Set basalt stone, 18x10x10 ins., 12 ins. in the ground, for $\frac{1}{2}$ sec. cor. marked $\frac{1}{2}$ on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, $5\frac{1}{2}$ ft. dist. and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
78.14	Intersect W. bdy. Township, 122 lks. N. of cor. to secs. 25 and 36, T. 1 N., R. 32 E. and set basalt stone, 9x8x7 ins., 6 ins. in the ground, for closing cor. to secs. 30 and 31 marked C C on E. face with 1 notch on S. and 5 notches on N. faces, and dug pits, 18x18x12 ins., N., E. and S. of stone, $5\frac{1}{2}$ ft. dist., raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it.