

Subdivisions of T. 1 N., R. 33 E.

Chains	
	<p>West on true line between secs. 19 and 30.</p> <p style="text-align: center;">Var. $20\frac{1}{2}^{\circ}$ East.</p>
40.00	<p>Set basalt stone, 10x8x8 ins., 6 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, $5\frac{1}{2}$ ft. dist. and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.</p>
46.46	<p>Spring branch, 4 lks., N.W.</p>
78.23	<p>Intersect W. bdy. Township, 130 lks. N. of cor. to secs. 24 and 25, T. 1 N., R. 32 E. and set basalt stone, 9x8x7 ins., 6 ins. in the ground, for closing cor. to secs. 19 and 30 marked C C on E. face with 2 notches on S. and 4 notches on N. faces. Dug pits, 18x18x12 ins., N., E. and S. of stone, $5\frac{1}{2}$ ft. dist., and raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it.</p>
	<p>Land, rolling. Grass scarce.</p>
	<p>Soil, 1st rate.</p>
	<p>North between secs. 19 and 20.</p>
	<p style="text-align: center;">Var. $20\frac{1}{2}^{\circ}$ East.</p>
40.00	<p>Set basalt stone, 12x9x4 ins., 6 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.</p>
80.00	<p>Set basalt stone, 12x10x8 ins., 8 ins. in the ground, for cor. to secs. 17, 18, 19 and 20 marked with 3 notches on S. and 5 notches on E. edges. Dug pits, 18x18x12 ins., in each sec. $5\frac{1}{2}$ ft. dist., raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it.</p>
	<p>Land, level.</p>
	<p>Soil, 1st rate.</p>
	<p>Grass scarce. Not cultivated.</p>
	<p>East on random between secs. 17 and 20.</p>
40.00	<p>Set temporary $\frac{1}{4}$ sec. cor. and at</p>
79.75	<p>Intersect N. and S. line, 12 lks. S. of cor. to secs. 16, 17, 20 and 21. Thence,</p>