

## Subdivisions of T. 1 N., R. 33 E.

Chains	bed of dry gulch marked 1/16 on N. face for 1/16 sec. cor. and raised mound of stone 1½ ft. high, 3½ ft. base over it.
63.50	Trail, N.W.
77.37	Intersect W. bdy. Township, 300 lks. N. of cor. to secs. 1 and 12, T. 1 N., R. 32 E., and set basalt stone, 12x10x10 ins., 8 ins. in the ground, for closing cor. to secs. 6 and 7 marked C C on E. with 5 notches on S. and 1 notch on N. faces. Dug pits, 18x18x12 ins., N. E. and S. of stone, 5½ ft. dist. and raised mound of earth 2 ft. high, 4½ ft. base over it. Land, rolling. Soil, 1st rate. Grass, scarce. Not cultivated. August 3, 1887.
	North on random between secs. 5 and 6. Var. 20° East. Set temporary ¼ and 1/16 sec. cors. at 20, 40 and 60 chains and at
76.00	Intersect N. bdy. Township, 68 lks. E. of cor. to secs. 5, 6, 31 and 32. Thence S. 29° E. on true line. Var. 20° East.
16.00	Deposited charred stake, 12 ins. in the ground, for 1/16 sec. cor. Dug pits, 18x18x12 ins., N. and S. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on W. face.
31.17	Trail, W.
36.00	Deposited charred stake 12 ins. in the ground for ¼ sec. cor. Dug pits, 18x18x12 ins., N. and S. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked ¼ S on W. face.
56.00	Deposited charred stake, 12 ins. in the ground, for 1/16 sec. cor. Dug pits, 18x18x12 ins., N. and S. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face.