

Sub-Subdivisions of T. 1 N., R. 33 E.

Chains	Commencing at 1/16 sec. cor, 20 chains N. of 1/4 sec. cor. between secs. 9 and 10.
79.40	<p>East on random through N$\frac{1}{2}$ of sec. 10. Var. 21° East. Set temporary 1/16 sec. cors. at 20, 40 and 60 chains and at Intersect E. bdy., 50 lks. N. of 1/16 sec. cor. Thence N.89°39'West, on true line. Var. 20° East.</p>
19.85	<p>Deposited charred stake, 12 ins. in the ground, for 1/16 sec. cor. Dug pits, 18x18x12 ins., in the ground, 5$\frac{1}{2}$ ft. dist., E. and W. of stake, raised mound of earth 1$\frac{1}{2}$ ft. high, 3$\frac{1}{2}$ ft. base over it and in East pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 on N. face.</p>
39.70	<p>Deposited charred stake, 12 ins. in the ground, for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5$\frac{1}{2}$ ft. dist., raised mound of earth 1$\frac{1}{2}$ ft. high, 3$\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.</p>
59.55	<p>Deposited charred stake, 12 ins. in the ground, for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of cor., 5$\frac{1}{2}$ ft. dist., raised mound of earth 1$\frac{1}{2}$ ft. high, 3$\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.</p>
71.00	Dry bed of creek, N.W.
79.40	<p>1/16 sec. cor. between secs. 9 and 10. Land, level. Soil, 2nd rate. No grass.</p>
	<p>East on random through S$\frac{1}{2}$ of sec. 2. Var. 20° East. Commencing at 1/16 sec. cor., 20 chains N. of S.W. cor. of sec. 2. Set temporary 1/16 sec. cors. at 20, 40 and 60 chains and at</p>