

Sub-Subdivisions of T. 1 N., R. 33 E.

Chains 39.97	Deposited charred stake, 12 ins. in the ground, for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft. dist. raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long; 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
59.96	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in East pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
79.95	1/16 sec. cor. between secs. 2 and 3. Land, slightly rolling. Soil, 1st rate. Very little grass and weed. October 28, 1887.
	East on random through S.½ of sec. 3. Var. 21° East. Commencing at 1/16 sec. cor. 20 chains N. of S.W. cor. of sec. 3. Set temporary 1/16 sec. cors. at 20, 40, and 60 chains and at
79.55	Intersect E. bdy., 45 lks. N. of 1/16 sec. cor. between secs. 2 and 3. Thence N.89°41'W. on true line. Var. 20° East.
19.89	Deposited charred stake, 12 ins. in the ground, for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of cor. 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in East pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
21.25	East branch of Tудie Willows.
39.76	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft.